

Data Center

Highbridge, England



Highbridge Data Center

Highbridge, North Somerset, UK

Our data center is a fully secure facility that provides Managed Hosting services. We are located in the Isleport Business Park, in North Somerset within one mile of M5 Junction 22 and adjacent to the A38 highway.

Site Specification

Total Floor Area

929 square meters across two data halls

Floor Loading

1500 kg/sqm

Clear Heights

3.65 meters minimum clear height

Loading Dock

Yes

Building Access

Redundant points of entry are available

Power System

Power

2.5 MW AC power with dual incoming feeds

Generator

Two 2250kVA standby generators configured for N+1

Fuel Tanks

48 hours of fuel on-site

UPS

N+1 with two 400kVA UPS systems



Data Center - Highbridge

Environmental

CRAC/HVAC

Ten 55kW and twelve 65kW CRAC/HVAC units configured as N+1

Fire Suppression

Primary – Inergen fire suppression systems with a secondary dry pipe pre-action sprinkler system

Security

Security

Dual-access control with ID cards and biometric scanners along with a CCTV system

Monitoring

Continuous monitoring of HVAC, power and building systems

Connectivity

Backbone

Tata Communications' global network connectivity is available. Connectivity to third-party providers is also available for redundancy.

Additional Services

Remote Hands

The facility is supported by an experienced team of technical, communications and facilities staff. We offer technical services in support of your planning, configuration and implementation requirements and will provide ongoing hand-and-eye operation through our 24x7x365 support operations center.



For more information on the Highbridge Data Center, please contact:

DataCenterSales@tatacommunications.com

www.tatacommunications.com